

Australian Government

Department of Education, Employment and Workplace Relations

## **CPCCLSF3001A Licence to erect, alter and dismantle scaffolding intermediate level**

Release: 1



# **CPCCLSF3001A** Licence to erect, alter and dismantle scaffolding intermediate level

### **Modification History**

Not Applicable

### **Unit Descriptor**

Unit descriptor

This unit specifies the outcomes required to erect, alter and dismantle scaffolding at the Intermediate level which includes use and operation of Cantilevered crane-loading platforms, Cantilevered and spurred scaffolds, Barrow ramps and sloping platforms, perimeter safety screens and shutters Mast climbers, and tube and coupler scaffolds (including tube and coupler covered ways and gantries) for licensing purposes.

### **Application of the Unit**

Application of the unit	This unit covers the scope of work to plan the job, select and inspect equipment, set up task, erect scaffold and scaffold equipment and dismantle scaffold and scaffolding equipment. This unit is based upon the National Standard for Licensing Persons Performing High Risk Work. This unit in its current form meets state and territory licensing requirements. Any alteration will result in a unit which is not acceptable to regulators for the purpose of licensing. This unit has a pre-requisite requirement. This requirement may be met by either the successful completion of the unit <i>CPCCLSF2001A Licence to erect, alter and dismantle</i> <i>scaffolding basic level</i> or holding a valid licence for basic scaffolding.

### **Licensing/Regulatory Information**

Refer to Unit Descriptor

### **Pre-Requisites**

**Prerequisite units** 

CPCCLSF2001A

Licence to erect, alter and dismantle scaffolding basic level

### **Employability Skills Information**

**Employability skills** This unit contains employability skills.

### **Elements and Performance Criteria Pre-Content**

Elements describe the essential outcomes of a unit of competency. Performance criteria describe the performance needed to demonstrate achievement of the element. Where bold italicised text is used, further information is detailed in the required skills and knowledge section and the range statement. Assessment of performance is to be consistent with the evidence guide.

### Elements and Performance Criteria

EI	LEMENT	PERFORMANCE CRITERIA
1.	Plan job.	<ul> <li>1.1. Task to be undertaken is assessed.</li> <li>1.2. Potential workplace <i>hazards</i> are identified.</li> <li>1.3. <i>Hazard control measures</i> are identified consistent with <i>appropriate standards</i> to ensure the safety of personnel and equipment.</li> <li>1.4. Site information is obtained.</li> <li>1.5. <i>Scaffold, associated equipment</i> and <i>scaffold equipment</i> are identified from site information and in consultation with appropriate <i>personnel</i> (where applicable).</li> <li>1.6. <i>Safety equipment</i> is identified.</li> <li>1.7. All <i>forces and loads</i> exerted on and by the scaffold and/or scaffolding equipment are determined and calculated.</li> <li>1.8. Appropriate <i>communication methods</i> are identified with appropriate personnel.</li> </ul>
2.	Select and inspect equipment.	<ul> <li>2.1. Scaffold, associated equipment and scaffold equipment are selected and inspected according to <i>procedures</i> and site information.</li> <li>2.2. Safety equipment is selected and inspected according to procedures.</li> <li>2.3. All defective scaffold, associated equipment, scaffold equipment and safety equipment are isolated according to procedures.</li> <li>2.4. All defective scaffold, associated equipment, scaffold equipment and safety equipment are reported and recorded according to procedures.</li> <li>2.5. <i>Communication equipment</i> is selected and inspected for serviceability (where applicable).</li> </ul>
3.	Set up task.	<ul> <li>3.1. Appropriate <i>hazard prevention/control measures</i> are applied to the work area according to procedures.</li> <li>3.2. Ground suitability is checked.</li> <li>3.3. Appropriate footings are prepared to support scaffold and scaffold equipment according to procedures and the appropriate standard.</li> <li>3.4. Scaffold and scaffold equipment are prepared for erection</li> <li>3.5. Fit safety equipment and secure according to procedures (where applicable).</li> <li>3.6. Scaffold and scaffold equipment are positioned for work application and <i>stability</i> according to procedures and the appropriate standard.</li> </ul>
4.	Erect scaffold and	4.1. Scaffold and scaffold equipment are erected

ELEMENT	PERFORMANCE CRITERIA
scaffolding	according to procedures and the appropriate
equipment.	standard.
	4.2. Work is conducted safely at heights including safe
	and effective use of safety equipment.
	4.3.Scaffold and scaffold equipment are erected consistent with site information.
	4.4. Appropriate communication methods are used to coordinate the tasks.
	4.5. Completed tasks are inspected for compliance with the appropriate standard.
	4.6. Handover certificate is completed as required and handed to appropriate personnel.
	4.7. Excess materials from the work area are removed (where applicable).

ELEMENT	PERFORMANCE CRITERIA
5. Dismantle scaffold and scaffolding equipment.	5.1.Scaffold and scaffold equipment are dismantled according to procedures and the appropriate standard.
	5.2. Work is conducted safely at heights including safe and effective use of safety equipment.
	5.3. Scaffold, associated equipment and scaffold equipment are inspected for damage and defects.
	5.4. All damaged and defective scaffold, associated equipment and scaffold equipment are tagged and isolated according to procedures.
	5.5.Hazard prevention/control measures are removed (where appropriate).
	5.6. All damaged and defective scaffold, associated equipment and scaffold equipment are reported and recorded according to procedures and appropriate action taken.

### **Required Skills and Knowledge**

#### **REQUIRED SKILLS AND KNOWLEDGE**

This section describes the skills and knowledge required for this unit.

#### **Required skills**

Required skills for this unit are:

- ability to erect scaffold and scaffolding equipment within the scope of the intermediate scaffolder
- ability to erect, level, plumb and stabilise scaffolds and scaffold equipment within the scope of the intermediate scaffolder
- ability to interpret manufacturer's specifications for plant and equipment
- ability to work safely at heights
- accurate interpretation of basic structural charts and structural plans
- correct application of all scaffolding equipment
- verify problems and equipment faults and demonstrate appropriate response.

#### **Required knowledge**

Required knowledge for this unit is:

- use of appropriate mathematical procedures for estimation and measurement of loads
- Commonwealth, state or territory OHS legislation and local government regulations, including standards and codes of practice relevant to the full range of

#### **REQUIRED SKILLS AND KNOWLEDGE**

techniques for undertaking intermediate scaffolding activities

- knowledge of principles relating to plant and equipment stability
- knowledge of types of scaffolding and their application
- knowledge of scaffold and scaffold equipment erection and dismantling techniques
- knowledge of types of scaffold and scaffold equipment, associated with intermediate scaffolding and their use/s
- risk assessment and control, including understanding of the hierarchy of control
- load capabilities of different types of scaffolding constructions
- understanding and application of organisational and workplace standards, requirements, policies and procedures for scaffolding
- application of safety equipment applicable to scaffolding
- understanding and application of the inspection and maintenance requirements for intermediate scaffold, associated equipment and scaffold equipment
- uses and limitations of tools and equipment, appropriate to scaffolding tasks and activities.

### **Evidence Guide**

#### **EVIDENCE GUIDE**

The evidence guide provides advice on assessment and must be read in conjunction with the performance criteria, required skills and knowledge, range statement and the Assessment Guidelines for the Training Package.

Overview of assessment	Successful assessment of this unit meets the competency requirement of the National Standard for licensing Persons Performing High Risk Work. State/Territory OHS regulators have mandated the use of Assessment Instruments and Instructions for Assessment endorsed by the national body responsible for OHS matters for the assessment of this unit.
Critical aspects for assessment and evidence required to demonstrate competency in this unit	<ul><li>A person who demonstrates competency in this unit must be able to provide evidence of the ability to:</li><li>Effectively communicate and work safely with</li></ul>
	others in the work area.
	• Effectively apply risk assessment and hazard management procedures at an intermediate scaffolder level.

• Effectively complete the planning, erection and

dismantling of scaffolding systems, in accordance with procedures, including a minimum of erect and dismantle the following:

- Cantilevered and spurred scaffolds
- Barrow ramps and/ or sloping platforms
- Tube and coupler scaffolds
- Cantilevered crane-loading platforms
- Mast climbers

Cantilevered, spurred and tube and coupler scaffolds to be of a minimum height of 5.0 metres above the supporting surface with full edge protection, for each work platform including toe boards and handrails.

- Apply safety screen to tube and coupler scaffold.
- Effectively conduct compliance inspections of scaffold and scaffold equipment for intermediate scaffolding.
- Complete handover certificate as required.

Context of and specific resources for assessment	<ul> <li>Assessment of the safe and effective application of knowledge and skill to workplace tasks (performance) must be undertaken using the National OHS endorsed Assessment Instrument.</li> <li>Assessment of performance must be undertaken either in the workplace or in a realistically simulated workplace setting.</li> <li>Assessors must ensure that the assessment in the workplace is organised to ensure that all the required equipment and materials and a suitable working area is made available to suit the assessment and the workplace.</li> <li>Assessment must occur under standard and authorised work practices, safety requirements and environmental constraints for intermediate scaffolding.</li> </ul>
	Applicants must have access to:
	• personal protective equipment (PPE) for the purpose of the Performance Assessment
	<ul> <li>appropriate safety equipment in safe condition</li> </ul>
	<ul> <li>appropriate scaffold and scaffold equipment in safe condition</li> </ul>
	<ul> <li>site information as described in the mandated assessment instrument</li> </ul>
	<ul> <li>communication equipment (e.g. fixed channel two way radios) where applicable</li> </ul>
	• appropriate personnel to assist with the erecting and dismantling of scaffold and scaffold equipment.
Method of assessment	Assessment must be conducted using the national OHS endorsed Assessment Instruments. These Instruments provide advice on their application. Assessment may be in conjunction with the assessment of other units of competency. The use of <b>'simulators'</b> in the assessment of this unit of competency is <b>not acceptable</b> . Assessment methods must confirm consistency and accuracy of performance together with application of underpinning knowledge. Assessment must confirm a reasonable inference that competency is not only able to be satisfied under the particular circumstance, but is able to be

transferred to other circumstances.

Guidance information for	Further information about endorsed assessment
assessment	instruments may be obtained from state/territory
	OHS regulators.

#### **Range Statement**

#### **RANGE STATEMENT**

The range statement relates to the unit of competency as a whole. It allows for different work environments and situations that may affect performance. Bold italicised wording, if used in the performance criteria, is detailed below. Essential operating conditions that may be present with training and assessment (depending on the work situation, needs of the candidate, accessibility of the item, and local industry and regional contexts) may also be included.

*Hazards* may include but not limited to:

- ground conditions (e.g. ground bearing pressure/s, back filled trenches, underground services, slopes)
- overhead hazards (e.g. power lines, service pipes) (minimum clearance distance from powerlines or electrical equipment as determined by relevant state authority or electrical supply authority.)
- traffic (e.g. pedestrians, vehicles, other plant)
- insufficient lighting
- environmental conditions (e.g. wind, lightning, storms)
- other site specific hazards (e.g. hazardous materials).

Refers to the systematic process of eliminating or reducing the risk to personnel and property through the application of controls. It includes the application of the hierarchy of control, the six-step preference of control measures to manage and control risk:

- elimination
- substitution
- isolation
- engineering control measures
- using safe work practices
- personal protective equipment.

Hazard control measures:

Appropriate standards may nclude:	<ul><li> codes of practice</li><li> legislation</li></ul>
	Australian Standards
	• manufacturer's specifications
	• industry standards (where applicable).
Site Information may include, but	• local conditions such as access and egress
not limited to:	• work method statements
not minicu to.	• site-specific job safety analyses and other documentation as required
	• task plans.
Scaffold may include but not	• all scaffolds at the basis level
imited to:	cantilevered and spurred scaffolds
	barrow ramps and sloping platforms
	• tube and coupler scaffolds (including tube and coupler covered ways and gantries)
	• cantilever loading platforms.
Associated equipment may include but not limited to:	<ul> <li>all associated equipment from basic scaffolding level</li> </ul>
	• independent adjustable props.
Scaffold equipment may include	• all scaffold equipment at the basic level
but not limited to:	mast climbers
	• screen and shutters.
Appropriate personnel may	• supervisors
nclude, but are not limited to:	• colleagues
	• managers who are authorised to take
	responsibility for the workplace or operations
	other scaffolders
	• other site personnel as applicable.
Safety equipment may include but	safety harness
not limited to:	energy absorber
	• lanyard
	• inertia reel.
Forces and Loads may include,	dead loads
but are not limited to:	live loads
	static load
	dynamic loads
	• wind loads.
Communication Methods may	• verbal and non-verbal language
include but not limited to:	
nclude but not limited to:	written instructions

#### **RANGE STATEMENT**

	communication signals
	• listening
	• questioning to confirm understanding, and appropriate worksite protocol.
<i>Procedures</i> may include but not limited to:	• manufacturer's guidelines (instructions, specifications or checklists)
	• industry operating procedures, relevant codes of practice
	• workplace procedures (work instructions, operating procedures, checklists)
	• reporting and recording procedures such as e.g. scaffold and scaffold equipment defects.
<i>Communication equipment</i> may include but not limited to:	<ul><li>fixed frequency two way radios</li><li>mobile phones.</li></ul>
<i>Hazard prevention/control</i> <i>measures</i> may include but not limited to:	<ul> <li>safety tags on electrical switches/isolators</li> <li>safety observer used inside exclusion zone (e.g. Spotter), to include the use of power line warning systems (e.g. Tiger tails)</li> <li>power disconnected by competent authority where applicable.</li> <li>traffic and pedestrian barricades and controls</li> <li>safe and adequate access / egress is</li> </ul>
	<ul><li>established</li><li>personal protective equipment</li><li>adequate illumination.</li></ul>
<i>Ground suitability</i> may include but not limited to:	<ul> <li>rough uneven ground</li> <li>backfilled ground</li> <li>soft soils</li> <li>hard compacted soil</li> <li>rock</li> <li>bitumen</li> <li>concrete.</li> </ul>
<i>Stability</i> may include but not limited to:	<ul> <li>ground bearing pressure</li> <li>sole plates/boards</li> <li>screw jacks</li> <li>levelling</li> <li>ties/guys.</li> </ul>

#### **RANGE STATEMENT**

### **Unit Sector(s)**

Unit sector

Construction

### **Co-requisite units**

**Co-requisite units** Nil

### **Functional area**

**Functional area**